### Hyper-Kamiokande Detector

Hide-Kazu TANAKA (University of Tokyo, ICRR)

for Hyper-Kamiokande Working Group

CRC Town Meeting, March 14th, 2014

### Outline

- Hyper-Kamiokande detector baseline design
  - Cavern construction
  - Tank construction
    - Lining, photo-sensor support, etc
- R&Ds for Hyper-Kamiokande
- Summary

# Key parameters of the baseline design

• Cavern size:

 $48m(W) \times 54m(H) \times 250m(L) \times 2$  caverns

- Cavern shape: oval shape (egg shape)
- Optically separated compartments: 5x2 = 10
- Water Volume:
  - •Total: 0.496x2=0.992 Megaton
  - ID volume: 0.74 Mton
  - Fiducial Volume: 0.056x10 = 0.56 Mton (25 x Super-K)
  - Depth of tank water: 48m
- Number of photo-sensors:
  - ID: ~99,000 20" photo-sensors (20% photo-coverage)
  - OD: ~25,000 8" photo-sensors (same coverage as SK)



Theal Longel: 247.5m (SCa

#### CAVERN CONSTRUCTION



### Detector location/site

- The candidate site locates under "Nijugo-yama"
  - Tochibora mine
  - ~8km south from Super-K
  - Identical baseline (295km) and off-axis angle (2.5deg) to T2K
- Overburden ~650m (~1755 m.w.e.)





### Geological survey at Tochibora-site

- The candidate site vicinity had been used for mining, and historically many surveys have been done in wide area and at several levels/depths.
  - ex. mapping the location of faults
- There are many existing tunnels and shafts at the around candidate site.
- The rock mass characterization has been done by mapping the existing tunnels and geological logging of rock core samples.

#### Overview of the geological survey



/

#### Rock mass characterization



From the survey results, rock mass characteristics are classified into 6 categories: A, B, CH, CM, CL and D (defined by CRIEPI). 'A' (blue) is the highest

grade rock and 'D' (red) is lowest.

Based on these results, established a model of the rock class distribution at HK tank locations.

#### (CRIEPI: The Central Research Institute of Electric Power Industry)

HK tank location

#### Initial stress measurements



Fig. 3.5 Stress Measurement Planar View and In-Plane Stress

### Cavern stability analysis

Side Wall Section



10

- Based on the survey results (rock mass characteristics and initial stresses), structural stability of caverns has been studied
  - Elasto-plastic, static analysis & adopt Hoek-Brown yield (failure) criteria
  - The excavation-steps take account in the studies
  - Include the cavern supporting material: shotcre Pre-Stressed (PS





- Plasticity region ~I3m at most (CM class) → affordable level
  - Proved in the existing underground facilities (ex. power plants)
- For all rock mass classes (B, CH, CM), HK caverns can be constructed by the existing excavation/support techniques. ...

#### Construction procedure

- Two major construction stages:
- Tunnel construction [~2 years]
  - Construct new tunnels, and widen the existing tunnels, arch tunnels, etc.
  - Construct the shafts/tunnels for muck (rock waste) transportation, belt conveyer tunnels, etc.
- Cavern construction [~3 years]
  - Excavate caverns and install prestressed anchors, etc
    - North and south caverns in parallel
  - Construct water purification rooms

#### **Tunnel construction**



#### Cavern construction



on





- Muck (rock waste) transported to Maru-yama using belt-conveyor
  - ~5 km long path from HK site (Tochibora)
  - Maximum excavation volume: 4,000 m<sup>3</sup> / day



 Need detailed survey/study on bedrock condition of Maru-yama

#### **Construction schedule a** 4. 6-3 **for Tochibora site**

HKプロジェ									ェクト エ事コ												工事工程表														3 1									
	数量	単 位			1	年度	ŧ					<b>Г</b> .Г	_	2年	度	1					3	3年月	度	Tal				-		4£	F度							5	年月	£				
			$\left  \right $	4 5	6	/ 8	9 10		12 1	2	3	4 5	6	/	5 9	10 1	1 12	1 2	3	4 5	6		9	10 1	12	1 2	3	4	5 6		8 9	10	11 12		2 3	4	5 0	6 /	8	9 1	201	12		2 3
			+				+		-		+					+	╈	ベルコ	ン稼	動開始	<u> </u>																╈	+	+	+	2012	·.1	++	
2 王要工事工程							_																	-													_		╞	┢			-	
2.179セス坑道		1式			Ē						_	-										┢┥┥	_	_	┿	-		_				┢┥┝	-	┝─┝	_		_	+	$\vdash$	┿	+		-	
	·v							h					-							C		+		╈	++	+		-	+		+	$\vdash$	-				-	╈	H	+	┢	-+	++	+
	·修理工場、休憩所	*****								5				-	F	4				D		$^{++}$		╈	$^{++}$	1	f			施	「工済	トレート み予定	区間				-		h	+	$\square$		-	1
2.1.1新規区間	304.6m、984.4m	569.0	m			3.6F 304.6	1 m)	2 (26	.5月 64.4m)	)												Π			Π			Т	-	仕上	げ吹	き付け	2.47	月	1			Π	Π	Т	Π			Π
212追切区問①	<u>施工済み予定/20m)</u> 275.1m	(1289.0)	m				- <u>k</u>		\$										T			$\left  \right $		-	╋		<u>.</u>		÷.	oo o	T	Ŀ,							$\square$					
2.1.2足切区间①	275.1	270.0					2.1	(275	5.1m)																					5	• -	, i	#表2.	677	· _				H	+				
2.1.3追切区間②	835.9m	835.9	m							╞					<b>φ</b>		TT					П			$\square$	T	Í					m								T				T
		ļ									6.3	3月(8	35.9	m)		_										~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~							-		_				Щ	_		_ <b>_</b>		
2.277泊-チ坑道	マーエルサー	617.0			┢━┣━	┿┥	_	$\vdash$	_	$\square$		4.4	月	_	╢┦		<u> </u>					┿┥		╋	++	-	-			┢╍┝╸		舗	装	┝──┝		┢─┢	_		$\vdash$	_	┉			+
		200.0	111 m		$\vdash$	┢╋		$\mathbb{H}$		ŀľ		-		Ťŀ	+ 3	0)1月 <b>0,⊢0</b>	(1)0.! I <b>0:0</b> 1	5月 十		+	-	⊢	-+	┢	+	-	┢	-	+	$\vdash$	$+^{\circ}$		Ť	្រុំ	±±(	が吹付	j	+	$\mathbb{H}$	+	+	÷	┿	+
201 1670日	2.4	196.0	m													<b>†   </b>	2	0.8月			~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~					~~~~~	~~~~								Î		•							
2.2.1 1段日	アーチ中央坑道	413.9	m											2 0		<b>4</b>	0.6月																8		┝									
	観測坑道	527.0	m											2.3	ΪI				-		~~~~					~~~~~																		
222 2段日	52./m × 10 <u>巩</u> 迫	629.2	m		h	+	_	$\vdash$	_	$\square$							+	Ť	-	<u>ج</u>	4.8	5月		<b>-</b>	++	-		-			+	$\vdash$	-	$\mathbb{H}$	+		-	╈	H	+	$\square$			+
2.2.3 3段目		93.4	m			$\dagger$	-	trt	-	$\square$		+2	1.52 空ずり	月 10 ピッ	53.4m 内50	n m)	m		-		1	0.	7月	4	中央均 99日	た道 806	m) .	-			-	ΙT	-	h	-		-	-	h	$\neg$	$\mathbf{T}$	, T		†
	水槽・ずりピット進入路	571.6	m											<b>.</b>		<b>-</b> የ								6		200													П					
2.2.4 4段目	機械組立坑道	447.3	m							、ルコン	0. /坑道	75月 [より]	02 402 1_* 27	.3m							~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~					6			*															
225 ずり運搬立坊	49./m×9 <u>巩</u> 担)			_	H	+	_	$\vdash$				-	$\square$	-	╈	<b>4</b>			-			+		┢╋╌	++	-		-			+		+	$\mathbb{H}$	+		-	╈	$\vdash$	╈	$\square$			
2.2.6 ずりピット	巾27m×高さ9m×長さ50m	1	基	-	h		-	Ħ				-	H			<b>k</b>					1	$\square$			$^{++}$	1	ţ	1	1		1	Ħ		Γt			-		h	1	$\square$			1
2.4 ベル トコンベア坑道															7	クセスキ	坑道よ	: 4 T																										
進備工	田山跡地道路整備		<del>,</del> †¢			<u>–</u> ¢		<b>∔</b> Ġ			ф						<b>ه</b>																				4	┢		-				
-370~ -200 BCT	坑口仮設備(200坑迫) · 進備工	1	可0		٦ <b>١</b>		-	ĪĪ		ΪÍ											~																_		$\vdash$	_				
	・吹き付けバッチャープラント						_																			~											_		$\vdash$	+			++	
	ロンクリートモービル)										_																				-								$\square$	_		_		_
	·修理用部品倉庫、休憩所 佐道堀削(下り)	12424	m				_ 拆	国削 1	11.3月												~~~~~										-						_		$\vdash$	_		_		
0~-200 вст	坑口仮設備(パートル坑道)	1242.4	式	<u> </u>		+	-	t t		$\square$		-	$\vdash$	-	┢╋	-	++		-		-	+			++	1			+		+	$\square$	1	h	-		-	+	H	+	$\square$		++	
	・吹き付けバッチャープラント						800000 0000000										$\square$				Ť	$\square$					Ĺ																	
	・排水タンク設置、配管																				1					1	ļ												Д			Ļ		
	・ヤード造成、既存設備撤去					+		┝──┝		┝╍┝		-	┝─┝	_	╇╋	_	┿┯┿					┿┿		4	╇┯┿		ļ					┝╍┝╸		┝╍╍┝					┢╍┝	_				
	·修理用部品扂庳、休息所	747.0	m		$\vdash$		扳	副削 6	5.8月	-	•	_	$\square$	-' i	▮ 屈削	! 7.0月	'+		-			┢┥						_			_				_		_		$\vdash$	+				
	坑道掘削 たり	806.7	m	-	H	+				貫通		休止	<u>2.0</u> 力	月	(FH山	<u>直送)</u>			-		+	$^{++}$			++	╈	h	+	+		╈	ht	-	$\vdash$	-		-	+	H	+	$\square$		+	
0~230BCT	坑口仮設備 230メートル坑道)	1	式		4		- <b>^</b>		II	函削 O .	).2 <mark>月</mark>										Ì																							
	坑道掘削 止り	1676.7	m		<b>-</b>		1	屈削 〕 ╡ タ ♯	11.0月	4 0 +	.8. *		1	- <del>.</del>	501						_				$\downarrow$	_	Ļ	_	_		_	Щ.	_		_			_	Щ	_		<b>i</b>		
	坑道掘削 たり			_	$\vdash$	「 掘肖	月 2.0	月(円)	山) —		副削	2.0月	。 <b>「</b> (円山	 _) <sup>*</sup>	5.07		+	++	_				(t =   )		3 00 +F	240		_	_						_		_		$\vdash$	_		-	_	
	<u>^ ルトコンヘ /-設置工</u>			-	$\vdash$	+	_	$\vdash$	_	H	-	-	H	-	╉╋	-	ΗŤ		-		+		紀水.	全進	へ哈切			_	+		+	┢──	-	┝─┢			-		$\vdash$	┿	┉	-		
純水装置室																		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~				2次科	1次約 1次約	地内 电水图			•			1 •2次	純水	 室アン	<u>カー</u>		0 FR - 7		++	<u>- 9</u>						
2.3水槽空洞																			-		┍┼╕	部振	副	14FX	の調査	ы <u>,</u>	1.1世		2段	アプロ の理論	ーチ	坑道		1	からの	掘削	-			4段	マフ の#	コーチ	-坑道	4
北侧北横灾河																			9			11		1	<b> </b>		ţ_ţ	-g-	<i>N</i> '5	の力出す	71			<u></u> _		1-1	4-	╇╼┛		۶Ť-	107 14		•	
北侧小帽空涧																					~~~~~~				100000000000000000000000000000000000000	~~~~~~	~~~~~							P					ſ	I				
				V												仮	曲 凶		V		-ד	↓ ↓ チ音	『掘削	J	+1段	アプロ		坑道		2F	<b>安</b> アフ	<u>p</u> +;	チ坑道	$\mathbb{H}$	3F	¥アフ らの#	(ローー・ 掘削	<b>手坑</b>	<b>邕</b>	4段 カト	rフロ の掘		卯道.	-
南側水槽空洞															1				-							JUジ 打出		1	<u>.</u>	20`	501		-		2					÷	Ħ			
		i	L İ	<u> </u>			_				- i											ΠÌ	T					Ī							5					· <b>P</b> -	<u>t-</u>		<u>+</u> •	<b>)</b>

### Other candidate site

- Mozumi-site would be a second choice, where potentially provides more overburden
  - >700m (cf. Tochibora-site: ~650m)
    - Preferable for low energy physics
  - Under Mt. Ikenoyama (near SK)
  - No geological survey in the past



- 250m long rock sampling (for rock characterization)
- ~14m (in total) rock samplings (for rock strength)
- Based on the survey results, the cavern stability analyses in progress
  - HK construction cost and schedule will follow
- Decision by HK physics sensitivity & cost/schedule





#### LINER AND PHOTO-SENSOR SUPPORT

### HK detector

- Hyper-K detector consists of 10 compartments which are optically separated
- One compartment consists of Inner Detector (ID) and Outer Detector (OD), like SK
  - ID uses 20" photo-sensors, ~20% photo-coverage
  - OD uses 8" photo-sensors, ~1% photo-coverage



#### **CROSS** Water containment system

Inner Detector

24000



• Plus, additional lining with a waterproof sheet

 To prevent mixing sump-water and tankwater

Drain lines are separated for sump-water and tank-water.



#### Water containment system

Polyethylene (HDPE) lining sheet has a number of studs protruding from one side, that fasten the lining sheet on the concrete.





- Enable to construct HDPE lining and concrete lining simultaneously
- HDPE sheets are welded together
- Holes on the lining sheet can be identified by pinhole test / spark testing

### Lining sheet testing

- Material compatibility testing
  - Soak in ultra-pure water & 1% gadolinium sulfate solution
- Tensile & creep testings
  - Tested the base material and welded part
- Pressure testings
  - Including 'pin hole' testing
  - Apply pressure up to 8kgf/cm<sup>2</sup>
  - Tested also the penetrating structure (used for anchors for the photo-sensor support)
- Confirmed HDPE lining satisfactory to HK





### Photo-sensor support

- Number of photo-sensors
  - Inner Detector: ~99,000 of 20" (20% photo-coverage)
  - Outer Detector: ~25,000 of 8" (identical coverage to SK)
- Stainless-steel (SUS304) supporting structure holds photo-sensors



### Supporting structure

- Structure designed by taking the material/equipments loads into account:
  - Photo-sensors and its housing,
  - Front-end electronics,
  - Power/signal/network cables,
  - Water pipes,
  - Calibration system,
  - etc, etc

ID PMT + housing	27.8kg/PMT								
OD PMT	1.7kg/PMT								
PMT cable (10m)	2kg/PMT								
HUB	5kg/HUB								
Network cable (10m)	2kg/HUB								
Load on the roof	100kg/m²								
Cables on the roof	0.15kg/m <sup>2</sup>								
Water system pipes	1.4kg/m (65A PVC)								
Calibration holes	200A SUS								



### Other designing work

- Major part of HK tank has been designed.
  - Include layout of water pipes, front-end electronics, cables, calibration holes, plug manholes, ... etc.



#### Lining and support construction

- Use a "movable" scaffolding to construct the lining (concrete lining, HDPE lining, etc)
  - Size of the scaffolding is about a compartment (50m)
- Move the scaffolding to the next compartment after the lining finished in a compartment
- Support structure construction begins in the compartment where the lining finished
  - Use 'long-arm' cranes









- Baseline: Install photo-sensors in a compartment where lining and support structure constructed
  - (Lining  $\rightarrow$  Support structure  $\rightarrow$  Photo-sensor)
- Possible options (but impact to safety and cost)
  - Install photo-sensors in parallel w/ support construction
  - Install photo-sensors during the water filling

#### Tank construction schedule

		年/月					_						_			4														_				
	項目	角	1 2 3	4 5 6	1	10 11 1	12 13 14	15 16 17	7 18 19 2	20 21 22	2 23 24	25 26 2	7 28 29	30 31 3	32 33 34	4 35 36	37 38 3	39 40 41	42 43 4	4 45 46	47 48 49	50 51 52	5 53 54 55	5 56 57 51	8 59 60	61 62 63	64 65 66	6 67 68 6	69 70 71	72 73 74	75 76 77	78 79 80	0 81 82 8	33 84
	岩盤掘削工																																	
	ロックボルトエ	製作・手間 現地施工	5																											Ì				1
	水槽構築工				手术铅	<u></u> ≣+ ~		施工者	学發																							Æ	a	ľ
	純水設備工				20400X																													Ħ
	①裏込めコンクリート	∽ 現地施□	=																															
	移動架台	設計 製作・手配 設計	5																															
	コンシリートエ (I#水・Dix)-ト・#約・型中等) ドレンエ	2001 製作・手配 設計	5								•																							
LINING	ロックボルトエ	- 設計 製作・手配	5																															
0	ライニング (一般部) ライニング		5					2																										
	(PMT支柱アンカー金物)	製作・手	5																	A														
	②PMT架構	現地施口																													•			
PMT &	架構	設計 製作・手配 設計	5					•																							*60	搬入		
	支柱 ア J ガー 玉初 PMT	製作・手配 設計 製作・手配	5																															
support	PMTカバー	設計 製作・手配	5																															
Support	PMT取付	製作・手配	5																															Ħ
	③シート	現地施工																																Ħ
	押え金物	設計 製作・手配	5																															
	タイベック	- 設計 製作・手配 設計	5																															
		製作・手	3																															
	<ul><li>④配管</li></ul>	現地施工																													Y			
	配管	設計 製作・手配	5																															
	の地球気は勝つてい	184645 T													8	<b>用</b> :段	計 (多	¥作図・	現寸)	)⊞														╢
	②地域気補貨コイル	設計														: 材: : 製:	料・音 作・輯	協手≣ 送	3															
		製作・手	<u>er            </u>													:現	地据作	t 		/#														
	⑥マンホールプラグ	現地施工																																$\ $
	マンホール	設計 製作・手配	2																															
		TRUCK-																																╢
	⑦ 满水 使知 機哭 · 司答 · 司给	- 現地施工 設計																																Ш
		製作・手配	5	╢∏						$H \square$				$+ \Pi$																			╢╢	

425 2 535 635 3 595

- Tank construction: ~2 years
  - Lining: I + years, PMT installation: ~I year
  - Two tanks construction in parallel.



#### NEW PHOTO-SENSOR R&D

### Photo-sensor candidates

- The baseline design uses 20" PMTs (SK type PMT)
- Photo-sensors w/ better performance beneficial for Hyper-K physics and cost
- New photo-sensors R&D are in progress
  - Hybrid Photo-detector (HPD)
  - Box and Line dynodes PMT
  - High Quantum Efficiency (HQE) tube
    - Applicable for all photo-sensor candidates



### Hybrid Photo-detector

- Hybrid Photo-detector (HPD) is a new type of photosensor with an avalanche diode, replacing metal dynode.
- HPDs have a better performances than standard PMTs:
  - <u>Timing resolution</u>: shorter e-multiplication process
  - <u>Collection efficiency</u>: higher operating voltage (~I0kV)
  - Lower cost: mechanically simple
- 8" HPDs prototypes are bing tested (see later slides)



	8"HPD	20"HPD	20"PMT
HV	~8kV	~8kV	~2kV
Gain	10 <sup>4</sup> -10 <sup>5</sup>	10 <sup>4</sup> -10 <sup>5</sup>	~I0 <sup>7</sup>
TTS(ns)	0.6	0.8(*)	5.5
C.E.	~97%	~95%(*)	~80%
AD dia.	5mm	20mm	-

(\*) expectation from field calculation. preliminary value

# High QE photo-sensor

- How ode applicable for all photo-sensors
  SK type PMT, box&line dynode PMT, HPD)
  ode technology identical for all sensors
- HQE technique has been developed by HPK, and achieved QE ~30%
  - cf. SK type PMT: ~22%
- 20" HQE PMT prototypes are being tested (see later slides)



# Testing in 200t Č detector

 New photo-sensors being tested in 200t water Cherenkov detector (EGADS detector)

7 m

- 5 High QE PMTs (20")
- 8 HPDs (8")
- and 227 SK type PMTs (20")
- Proliminary tosting regults

#### EGADS 200t tank





#### Dark rates Measured in 200t water Č detector

8-inch HPDs



• HPDs and HQE PMTs dark rates at Ip.e.: I~8kHz  $\rightarrow$  Similar level to SK type PMTs



- HPDs show better TTS than SK style/HQE PMTs
  - Pre-amplifier impacts to TTS (can be improved)

#### Box & Line dynodes PMT

- Higher photo-electron collection efficiency (93%)
  - Larger acceptance of 1st dynode
- Fast time response (TTS: 2.7ns)
  - Electron multiplication path almost identical
- 20" Box & Line PMT prototype just delivered to Kamioka and start the testing



### Sensor R&D status & plan

- 8" HPDs and 20" HQE PMTs prototypes being tested in 200t water Č detector (previous slides)
  - Direct comparison with SK type PMTs
  - Long term operation experience: stability and lifetime of the devices
- The first prototype of 20" HPDs and 20" Box & Line dynodes PMTs just delivered
  - with HQE photo-cathode
  - Will evaluate the performance & identify possible problems and feedback to the final design
- Plan to install 20" HPD and B&L PMT in 200t water Cherenkov detector after the Lab testing

## Other R&Ds

Rn Free Air Generator (400Nm<sup>3</sup>/h)

- Photosensor housing
  - ex. implosion test
- Water system
- Readout electronics
- Calibration system
- Software development
- MC. The Philipposition Srmprotteration

": PMTs newly installed at SK-III

Design of near detector(s)

)UD



thin international



ne location of "standard PMTs" inside the SK inner detector.



<sup>γ</sup> (Ni captured) ~9MeV

Tuesday, January 15, 13 Figure 8: The observed charge differences between the first and second measurements in p calibration for checking reproducibility. It was checked using 50 of the 420 standard

#### Summary

- Hyper-K detector baseline design is ready
  - Detector construction cost and schedule evaluated
  - Technical design documents available shortly
- Design optimization and further cost reduction being investigated
- Several R&Ds and prototype testings are progressing in international working groups
  - Photo-sensors, software, water system, electronics, calibration, etc.
- For further details, see slides at HK meetings:
  - <u>http://indico.ipmu.jp/indico/conferenceDisplay.py?</u>
    <u>ovw=True&confld=29</u> (4th HK Open Meeting)
  - cf. next (5th) Hyper-K Open Meeting: July 19~21

# Supplements

#### Cavern shape

- Analyzed cavern stability for other cavern shapes
- Depth of plasticity region:
  - Oval shape (Baseline): ~14m
  - Straight wall (A): ~15m
  - Straight wall (B): ~21m
- For CM-class or worser rock mass, the depth of plasticity region for straight wall is beyond the manageable level with existing techniques.

Oval shape (Baseline) Straight wall (A) Straight wall (B)



#### Wire support options



PMT supporting by wires has also been studied

- →Found the construction cost is comparable (even higher)
- Wire termination requires special works and parts
- Devices to give initial tensions and additional tensions when a wire stretches afterwards

